# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17846

## APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/01/2015-16

**Improvements to Roads and Drains at Hanuman Layout and Ramachandrapura in ward No 10 Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K SHANKAR REDDY | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 400 | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 70.0 | Rupees Seventy Only |
| 2 | 60 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 4600.0 | Rupees Four Thousand Six Hundred Only |
| 3 | 960 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 14/ Item No. 4.31/ PWD SR 2010-11 | Sqm | 266.3 | Rupees Two Hundred Sixty Six and Thirty Paise Only |
| 4 | 126 | Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work | Cum | 5800.0 | Rupees Five Thousand Eight Hundred Only |
| 5 | 6.93 | Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work | Tonne | 78300.0 | Rupees Seventy Eight Thousand Three Hundred Only |
| 6 | 360 | Providing and fixing Precast RCC Slabs as per approved design, Specificiation and Direction Engineer-in-Charge. | Sqm | 1400.0 | Rupees One Thousand Four Hundred Only |

K. Sankar Reddy

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

3/2/16

| | | | | |
|---|---|---|---|---|
| 400 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 70.0 | Rupees Seventy Only |

K. Sankar Reddy
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30.1.17

2.5.16 (8) Months

41389-
35476-